

# BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2014-15/RD/WORK\_INDENT16932

## APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/10/2014-15, Date: 21.02.2015

**Providing Concrete Roads in Amruthahalli S.C Colony 8th and 9th cross in Ward no 07 Byatarayanapura**

| Sl. No. | Approved Qty. | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Unit | Approved Tender Rates of |                                               |
|---------|---------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|--------------------------|-----------------------------------------------|
|         |               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |      | P SHEKAR GOWDA           |                                               |
|         |               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |      | In Figures               | In Words                                      |
| 1       | 113.16        | KSRRB 300-1. Earth work excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications MORTH chapter 3.                                                                                                           | cum  | 90.0                     | Rupees Ninety Only                            |
| 2       | 597.9         | KSRRB 300-58. Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per specifications.                                                                                                                                                                                                                      | cum  | 4.0                      | Rupees Four Only                              |
| 3       | 119.58        | KSRRB 300-64.2. Extra for watering the earth to bring the earth upto required optimum moisture content with mechnery including cost of all labour, HOM of machineries complete as per specifications.                                                                                                                                                                                                                                                           | Cum  | 2.0                      | Rupees Two Only                               |
| 4       | 89.69         | KSRB 4-1.3 Providing and laying cement concrete using 40mm and down size granite jelly of ready mix concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., including smooth finish in CM 1:3, with all lead and lift etc., complete. (exculsive of cost of steel, fabrication and plastering charges) Ready mixed Cement concrete for Beams, Columns, Staircase and Roof with M-20 (1:1.5:3) (Cement-341 Kg/cum) | Cum  | 4750.0                   | Rupees Four Thousand Seven Hundred Fifty Only |
| 5       | 59.79         | Providing and laying cement concrete using 20mm and down size granite jelly of ready mix concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., including smooth finish in CM 1:3, with all lead and lift etc., complete. (exculsive of cost of steel, fabrication and plastering charges) Ready mixed Cement concrete for Beams, Columns, Staircase and Roof with M-20                                          | Cum  | 5700.0                   | Rupees Five Thousand Seven Hundred Only       |
| 6       | 597.9         | Vaccum de-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery, Screed Vibratory, Power Floater, blade and disc etc., with all lead and lift.                                                                                                                                                                                                                    | Sqm  | 90.0                     | Rupees Ninety Only                            |
| 7       | 90            | Providing groove cutting for width of 5mm to 10mm and depth 80mm-100mm including cost of cutting machine, generator & HOM of machinery, including cost of blade,coolant etc., including cleaning of groove & providing sand and hot bitumen fillars, and filler metal etc., including cost of conveyance of all materials, labour, lead and lift charges and all other incidental charges as per drawing and as per specifications. for concrete pavement       | Rmtr | 110.0                    | Rupees One Hundred Ten Only                   |

*P. Shekar*

H.V. 4 *[Signature]*  
M.V. (M.V.) 19/1/16

| Sl. No. | Approved Qty. | Description                                                                                                                                                                                                                                                                                                                                                                                                                                         | Unit | Approved Tender Rates of |                                               |
|---------|---------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|--------------------------|-----------------------------------------------|
|         |               |                                                                                                                                                                                                                                                                                                                                                                                                                                                     |      | P SHEKAR GOWDA           |                                               |
|         |               |                                                                                                                                                                                                                                                                                                                                                                                                                                                     |      | In Figures               | In Words                                      |
| 8       | 12.96         | KSRB 2-2.1 : Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications.           | cum  | 150.0                    | Rupees One Hundred Fifty Only                 |
| 9       | 12.96         | KSRB 4-1.2: Providing and laying in position plain cement concrete of I mix M10 With OPC cement @ 220 Kgs with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.                | cum  | 4900.0                   | Rupees Four Thousand Nine Hundred Only        |
| 10      | 5.76          | KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS                                                                                                                                      | cum  | 3650.0                   | Rupees Three Thousand Six Hundred Fifty Only  |
| 11      | 8.39          | KSRB 4-6.1 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specificaltons.                                                                                                                                                                                                 | sqm  | 230.0                    | Rupees Two Hundred Thirty Only                |
| 12      | 3.31          | Providing and laying cement concrete using 20mm and down size granite jelly of ready mix concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., including smooth finish in CM 1:3, with all lead and lift etc., complete. (exculsive of cost of steel, fabrication and plastering charges)Ready mixed Cement concrete for Beams, Columns, Staircase and Roof with M-20 (1:1.5:3) (Cement-3320Kg/cum) | cum  | 5750.0                   | Rupees Five Thousand Seven Hundred Fifty Only |
| 13      | 0.59          | KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.Tonn              | qtl  | 78000.0                  | Rupees Seventy Eight Thousand Only            |
| 14      | 19.2          | KSRB 15.1.3 – do – Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.                                                                                                                                                                                                             | Sqm  | 90.0                     | Rupees Ninety Only                            |
| 15      | 113.16        | Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 5.00 Km                                                                                                                                                                                                                                                                                                              | Cum  | 76.0                     | Rupees Seventy Six Only                       |

*P. Shekar Gowda*  
Signature of the Contractor

*H. V. S. Linga*  
Executive Engineer  
Byarayanapura Division  
BBMP, Bangalore - 92  
19/1/16